WATER-SUPPLY AND STORES DIVISION.

Dated 9th April 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Water-Supply and Stores Division, up to the 20th April 1912, for the undermentioned tools required for the Water-Supply and Stores Division. The work should be completed by the 1st June 1912.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the from given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (100) one hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the supply of tools;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Southern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

List of tools required.

Serial No.	*Names of tools*	*Number required.*
1.	Tampers, flat, C. I., about 16 lbs. each	162
2.	Buckets, galvanized, revetted, about 6 lbs. each	53
3.	Water casks, 6" long	2
4.	Locks, pad, Chubb's, 2" size	6
5.	Do $2\frac{1}{2}$" size	6
6.	Locks, pad, Aligarh, 2" size	9
7.	Do $2\frac{1}{2}$" size	8
8.	Do 3" "	3
9.	Do $1\frac{1}{2}$" "	4
10.	Hammers, claw	6
11.	Jumpers, steel, about 16 lbs. "Hen trade mark" per lb.	50
12.	Vice, hand, 6" size	3
13.	Flat plier, 6"	1
14.	Round nose, 6"	1
15.	Cutting plier, 6"	1
16.	Cast steel carpenters' brace with bits	3
17.	Carpenter's drawing knives	1
18.	Do spoke shaver	1
19.	Hammers, sledge, 14 lbs. each	62
20.	Bellows, English, 30" width	1

K. SRINIVASA AIYANGAR,
Executive Engineer.

BANGALORE DIVISION.

Dated 4th April 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 23rd April 1912, 5 P.M., for completing the open verandah and porches of Sir Sheshadri Iyer Memorial Hall at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1912.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for completing the open verandah and porches of Sir Sheshadri Iyer Memorial Hall at Bangalore;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

No.	*Items of work*	*Per*	*Quantity*
	Open verandah.		
1.	Cut stone pillars with caps and bases	Each	6
2.	Steel girders including fixing, etc., complete ...	Cwt.	18
3.	Pukka terrace with arch, etc., complete	Sq.	3·38
4.	Brick in chunam, parapet, balustrade	R. ft.	46
5.	Cut stone, plinth slabs, under pillars	C. ft.	23
6.	Chunam plastering	Sq.	3·50
7.	Flooring with Cuddappa slabs, etc., complete ...	,,	165
8.	Parapet with cut stone cornice	R. ft.	46
9.	Brick in chunam, cornice at top $1\frac{1}{4}' \times 1\frac{1}{4}$	,,	46
10.	Stone in chunam, superstructure	C. ft.	174
11.	Unforeseen charges that may be required for any extra ornamentation.	Lump sum.	
	Construction of porch.		
1.	Steel girders including fixing, etc., complete ...	Cwt.	40
2.	Pukka terrace with arch, etc., complete	Sq.	4·41
3.	Brick in chunam, parapet, balustrade	R. ft.	84
4.	Brick in chunam, cornice at top $1\frac{1}{4}' \times 1\frac{1}{4}'$ ornamental ...	,,	84
5.	Cut stone bases	C. ft.	75
6.	Cut stone shafts	,,	403
7.	Capitals with stone slabs and terracotta ornamental ...	Each	12
8.	Cast iron down pipes with painting, etc.	R ft.	40
9.	Unforeseen charges that may be required for any extra ornamentation.	Lump sum.	
	Quadrant wall.		
1.	Earthwork, excavation	C. yd.	4
2.	Concrete foundation	C. ft.	45
3.	Stone in chunam foundation	,,	60
4.	Stone in chunam superstructure	,,	383
5.	Cut stone moulding, ornamental	,,	26
6.	Do plain moulding	,,	24
7.	Servants stair case	Each	2
8.	Brick in chunam coping	R. ft.	15
9.	Unforeseen charges that may be required for any extra ornamentation.	Lump sum	
	Completion of terrace, etc.		
1.	Completing terrace cornice, parapet, etc., of two latrines	Do	

H. D. RICE,
Executive Engineer.